BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2023-24/OW/WORK_INDENT2338

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/12/2023-24 Dated: 13-02-2024

APPROVED TENDER SCHEDULE - B

Item-2

Name of Work:-Construction of Additional floor to Kenchenahalli Samudaya Bhavana in ward No 01

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
1	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge. Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum. (Tipper 10 m3) Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road Taking output 10 t load and lead 10 km = 100 t.km	Cum	0.78	2192.82	Two Thousand One Hundred NinetyTwo Paise EightyTwo Only
2	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	3.93	13310.81	Thirteen Thousand Three Hundred Ten Paise EightyOne Only
3	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	8.14	12527.82	Twelve Thousand Five Hundred TwentySeven Paise EightyTwo Only
4	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	17.16	11744.83	Eleven Thousand Seven Hundred FourtyFour Paise EightyThree Only

Executive Engineer
Yelahanka Division

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
5	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.	Tonne	5.45	102358.38	One Lakh Two Thousand Three Hundred FiftyEight Paise ThirtyEight Only
6	Providing Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work	Cum	40.74	9910.08	Nine Thousand Nine Hundred Ten Paise Eight Only
7	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	208.66	405.05	Four Hundred Five Paise Five Only
8	Providing 15 mm cement plaster with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	153.62	418.78	Four Hundred Eighteen Paise SeventyEight Only
9	Providing 12 mm cement plaster with cement mortar 1:6 (1 cement:6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	90.80	275.76	Two Hundred SeventyFive Paise SeventySix Only
10	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge..	Sqm	453.08	114.42	One Hundred Fourteen Paise FourtyTwo Only
11	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer in-charge.	Sqm	208.66	60.64	Sixty Paise SixtyFour Only
12	Finishing walls with textured exterior paint of required shade :New work (Two coats applied @ 3.28 L/10 m²) over and including priming coat of exterior primer applied @ 2.20kg/10 m² to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	208.66	323.81	Three Hundred TwentyThree Paise EightyOne Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Pal
BANGALORE - 560064

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
13	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m² over and including one coat of Special primer applied @ 0.75 L/10 m² with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life)	Sqm	244.42	180.78	One Hundred Eighty Paise SeventyEight Only
14	Providing and laying Cement concrete pavement with 1:2:4 for commercial & residential building floors, hardpaths, footpaths using 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size, including finishing complete as per Engineer incharge.	Sqm	9.08	7627.36	Seven Thousand Six Hundred TwentySeven Paise ThirtySix Only
15	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed , including cost of materials, mortar, labour, curing complete as per specifications.	Sqm	106.13	6096.39	Six Thousand NinetySix Paise ThirtyNine Only
16	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	Kgs	216.00	209.39	Two Hundred Nine Paise ThirtyNine Only
17	Providing & fixing of 3 track x 2 panel sliding windows made out of multi chambered UPVC (Matching to RAL-9016) sections and with minimum TiO2 (Titanium Dioxide) at 6PHR with TPE (Thermo Plastic Elastomer) and lead free gaskets grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&Ps shall not be made)	Sqm	4.80	7705.17	Seven Thousand Seven Hundred Five Paise Seventeen Only
18	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.	Cum	0.07	157986.88	One Lakh FiftySeven Thousand Nine Hundred EightySix Paise EightyEight Only
19	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures)	Sqm	3.15	8517.56	Eight Thousand Five Hundred Seventeen Paise FiftySix Only

Executive Engineer
Yelahanka Division,
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
20	Painting wood work with Deluxe Multi Surface Paint of required shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @0.75 L/10 m² of approved brand and manufacture to give an even shade including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, sand papering and knotting , cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (KPWD SR 2023-24, V-II, Item No.8.33.2, Page No.46)	Sqm	6.30	157.89	One Hundred FiftySeven Paise EightyNine Only
21	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @ 0.80 L/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	6.30	159.04	One Hundred FiftyNine Paise Four Only
22	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Kgs	84.00	646.48	Six Hundred FourtySix Paise FourtyEight Only
23	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU wate proofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6 kg/m2 to achieve final DFT (Dry Film Thickness) of 1mm including prime coat of epoxy primer @150 g/m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification..	Sqm	100.96	934.82	Nine Hundred ThirtyFour Paise EightyTwo Only
24	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	2.36	13310.81	Thirteen Thousand Three Hundred Ten Paise EightyOne Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
25	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	4.21	12527.82	Twelve Thousand Five Hundred TwentySeven Paise EightyTwo Only
26	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	8.62	11744.83	Eleven Thousand Seven Hundred FourtyFour Paise EightyThree Only
27	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.	Tonne	2.85	102358.38	One Lakh Two Thousand Three Hundred FiftyEight Paise ThirtyEight Only
28	Providing Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work	Cum	24.99	9910.08	Nine Thousand Nine Hundred Ten Paise Eight Only
29	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	127.03	405.05	Four Hundred Five Paise Five Only
30	Providing 15 mm cement plaster with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	88.84	418.78	Four Hundred Eighteen Paise SeventyEight Only
31	Providing 12 mm cement plaster with cement mortar 1:6 (1 cement:6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	50.56	275.76	Two Hundred SeventyFive Paise SeventySix Only

Executive Engineer
Yelahanka Zone
Bruhat Bangalore Mahanagara Pa
BANGALORE

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
32	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge..)	Sqm	266.43	114.42	One Hundred Fourteen Paise FourtyTwo Only
33	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	127.03	60.64	Sixty Paise SixtyFour Only
34	Finishing walls with textured exterior paint of required shade :New work (Two coats applied @ 3.28 L/10 m²) over and including priming coat of exterior primer applied @ 2.20kg/10 m² to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	127.03	323.81	Three Hundred TwentyThree Paise EightyOne Only
35	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m² over and including one coat of Special primer applied @ 0.75 L/10 m² with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life)	Sqm	139.40	180.78	One Hundred Eighty Paise SeventyEight Only
36	Providing and laying Cement concrete pavement with 1:2:4 for commercial & residential building floors, hardpaths, footpaths using 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size, including finishing complete as per Engineer incharge.	Sqm	5.06	7627.36	Seven Thousand Six Hundred TwentySeven Paise ThirtySix Only
37	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed , including cost of materials, mortar, labour, curing complete as per specifications.	Sqm	53.47	6096.39	Six Thousand NinetySix Paise ThirtyNine Only
38	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	Kgs	216.00	209.39	Two Hundred Nine Paise ThirtyNine Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Pal
BANGALORE - 560064

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
39	Providing & fixing of 3-track x 2-panel sliding windows made out of multi chambered UPVC (Matching to RAL 9016) sections and with minimum TiO2 (Titanium Dioxide) at 6PHR with TPE (Thermo Plastic Elastomer) and lead free gaskets grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm 2.5mm. Maximum possible size 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	4.80	7705.17	Seven Thousand Seven Hundred Five Paise Seventeen Only
40	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.	Cum	0.07	157986.88	One Lakh FiftySeven Thousand Nine Hundred EightySix Paise EightyEight Only
41	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures)	Sqm	2.52	8517.56	Eight Thousand Five Hundred Seventeen Paise FiftySix Only
42	Painting wood work with Deluxe Multi Surface Paint of required shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @0.75 L/10 m² of approved brand and manufacture to give an even shade including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, sand papering and knotting , cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	5.04	157.89	One Hundred FiftySeven Paise EightyNine Only
43	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @ 0.80 L/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	5.04	159.04	One Hundred FiftyNine Paise Four Only
44	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Ltr	1000.00	10.20	Ten Paise Twenty Only
45	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal dia Pipes	Mtr	80.00	360.26	Three Hundred Sixty Paise TwentySix Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Pa

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
46	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 32 mm nominal dia Pipes	Mtr	80.00	453.16	Four Hundred FiftyThree Paise Sixteen Only
47	Providing and fixing Brass full way valve gate with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	Nos	2.00	621.96	Six Hundred TwentyOne Paise NinetySix Only
48	Providing and fixing Brass full way valve gate with C.I. wheel of approved quality (screwed end) : 32 mm nominal bore	Nos	2.00	677.47	Six Hundred SeventySeven Paise FourtySeven Only
49	Providing and fixing gun metal non- return valve of approved quality (screwed end) : 32 mm nominal bore Vertical	Nos	1.00	1047.92	One Thousand FourtySeven Paise NinetyTwo Only
50	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 100 mm diameter	Mtr	75.00	329.67	Three Hundred TwentyNine Paise SixtySeven Only
51	Supplying heavy gauge PVC conduit pipe..... dia confirming to IS 2509 with suitable size benda, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.	Mtr	100.00	83.42	EightyThree Paise FourtyTwo Only
52	Supplying..... mm dia 2mm/2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.	Mtr	100.00	80.33	Eighty Paise ThirtyThree Only
53	Groove cutting in the wall supplying.....dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out conduit wherever necessary.	Mtr	100.00	81.36	EightyOne Paise ThirtySix Only
54	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of approved make etc.	Each	30.00	143.16	One Hundred FourtyThree Paise Sixteen Only
55	d)180x90x65mm	Each	30.00	165.81	One Hundred SixtyFive Paise EightyOne Only
56	e)200x90x65mm	Each	30.00	184.35	One Hundred EightyFour Paise ThirtyFive Only
57	Supplying and fixing PVC/metal conduit accessories.(3/5) b)25mm junction box	Each	20.00	57.67	FiftySeven Paise SixtySeven Only
58	c) 32mm deep junction box	Each	20.00	62.82	SixtyTwo Paise EightyTwo Only
59	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work cpmplete. a)12"x"12"x3" (330x300x76mm)	Mtr	20.00	123.59	One Hundred TwentyThree Paise FiftyNine Only

Executive Engine
Yelahanka Division
Yelahanka Zone

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
60	b)12x9"x3" (300x228x76)	Mtr	20.00	118.44	One Hundred Eighteen Paise FourtyFour Only
61	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet. Short point upto 3Mtr from tapping point to out let via switch	Point	10.00	293.52	Two Hundred NinetyThree Paise FiftyTwo Only
62	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet. b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch (Each point)	Point	10.00	405.78	Four Hundred Five Paise SeventyEight Only
63	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire copper PVC insulated multi strand 2x1.5Sqmm copper wire (confirming to IS-694:and latest amendments) without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. a) Short point up to 3Mtr from tapping point to out let via switch box	Point	10.00	277.04	Two Hundred SeventySeven Paise Four Only
64	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire copper PVC insulated multi strand 2x1.5Sqmm copper wire (confirming to IS-694:and latest amendments) without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box	Point	10.00	390.33	Three Hundred Ninety Paise ThirtyThree Only
65	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. e) 6Moudule	Point	35.00	241.00	Two Hundred FourtyOne Only
66	Supplying and fixing of modular switch & connected accessories on existing modular switch plate.	Each	25.00	105.05	One Hundred Five Paise Five Only
67	Stepped Fan Regulator Two Module	Each	8.00	367.67	Three Hundred SixtySeven Paise SixtySeven Only
68	16A One Way Switch	Each	4.00	185.38	One Hundred EightyFive Paise ThirtyEight Only
69	32A DP Switch	Each	2.00	335.75	Three Hundred ThirtyFive Paise SeventyFive Only
70	6/16A Universal Socket	Each	10.00	243.06	Two Hundred FourtyThree Paise Six Only

Executive Engineer
Yelahanka Division
Yelahanka Zone

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
71	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply &completely wired on existing box	Each	5.00	665.32	Six Hundred SixtyFive Paise ThirtyTwo Only
72	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. a. 1 sqmm.	Mtr	150.00	19.57	Nineteen Paise FiftySeven Only
73	1.5Sqmm	Mtr	150.00	26.78	TwentySix Paise SeventyEight Only
74	6Sqmm	Mtr	75.00	94.75	NinetyFour Paise SeventyFive Only
75	10Sqmm	Mtr	30.00	171.99	One Hundred SeventyOne Paise NinetyNine Only
76	16Sqmm	Mtr	50.00	327.51	Three Hundred TwentySeven Paise FiftyOne Only
77	Supplying and fixing of PVC casing and capping on the wall or ceilng using necessary materials like bends, screws at an interval of 300mm .... Etc as required. a) 20mm	Mtr	100.00	28.84	TwentyEight Paise EightyFour Only
78	Supplying PVC/GI flexible conduit pip 20mm dia fixing on surface over inverted wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pipe terminated completely. 20mm	Mtr	100.00	19.57	Nineteen Paise FiftySeven Only
79	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws. b) 110mm	Nos	15.00	21.63	TwentyOne Paise SixtyThree Only
80	Supplying a 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slap.	Nos	20.00	12.36	Twelve Paise ThirtySix Only
81	Supplying of 1 x 4 feet -PVC Batten with integrated LED tube 20 22 W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI 80. Power Input: 220-240V 50 60Hz & Power factor 0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition	Nos	30.00	710.63	Seven Hundred Ten Paise SixtyThree Only
82	Supply of round square recess surface mounted rolling type LED Down light with W GU 10 LED Lamp Rib Fabricated from diecast aluminium with white powder coated prewired to mains connector & has swivelling unit of aluminium die cast eye ball & LED Lamp position retained by circular wire spring, with Life of 25000 burning hours & 70% lumen maintenance with CRI 80. Power Input 220 240V 50 60Hz & Power factor 0.9 along with CE approved. 2years Warranty against any manufacturing defect working under standard electrical condition LED square or round down light 10-12W	Nos	20.00	911.46	Nine Hundred Eleven Paise FourtySix Only

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.T S Kothanda Raju(Proprietor R K CONSTRUCTIONS, Proprietor SHREE CHARAN CONSTRUCTIONS)	
				Rate	Rate in words
83	Supplying of Ceiling Fan with Capacitor rating As per guideline of BEE 5 star rating and IS:374/79 and also comply with IS: 1709/1984 with latest amendment, Rated voltage 220 V/50 Hz, Rated power input 48 W +/- 10 %, Rated current As per IS:374/79, Rated power factor 0.9 lagging(min), Rated speed 350 +/- 10% RPM, Rated air delivery 210 +/- 10% Cubic Meter Minimum, Rated service value 4.2 CMM / W, Three Blades of blade leaf 1.05 mm thick Aluminium Alloy sheet, Class B motor insulation, Bearing Two ball bearings, Top 6202, Bottom 6201, as per IS specification, Motor winding. Temp rise Shall not exceed 75 deg C over and ambient of 40 0C by resistance method at 245 V, Insulation resistance Shall not be less than Two Mega Ohms (2M Ohms), Leakage current Should not exceed 210 Micro Amp, Power input, W& current, Air Delivery & Fan Speed as per IS:374/1979 with latest amendment, 2 year manufacturer Warranty. 48" Sweep 5 Star (1200 mm)	Each	10.00	2757.04	Two Thousand Seven Hundred FiftySeven Paise Four Only

Signature of the Contractor

Executive Engineer
Yelahanka Division
BBMP, Bengaluru-64

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064